




We Show Up



We Bring It



We Do It Right

Metro Blvd. Curtain Wall Replacement

7201 Metro Blvd. is an office building that had a glass curtain wall covering its entire 9-story height. Unfortunately, employees inside the building were unable to see out of the glass entirely, and it did not allow daylight to stream into the office building.

THE CHALLENGE

The upper floors of the building had a knee wall that looked like glass from the outside. However, there was only a short vision panel for exterior viewing and to allow daylight inside the building. Our client, PCL Construction, asked Brin Contract Glazing to assist in reconstruction of the glass curtain wall to enhance visibility from both inside and outside of the building.

OUR SOLUTION

Brin Contract Glazing collaborated with the contractor and the design team to ensure the success of the project. The project started with removing the existing glass from the 2nd through 9th floors. Typically, this type of project would take 2-3 weeks to get the window opening sealed back up, during which time the floors would be exposed to the elements. By utilizing a crane to get all the glass installed quickly, Brin was able to enclose the opening within a few days, which protected the floors from weather-related damage.

RESULTS ACCOMPLISHED

Brin Contract Glazing replaced out a large section of the façade from the 2nd through the 9th floors and installed a glass curtain wall that was visible all the way through on all 9 floors. In one day, Brin was able to install 53 pieces of insulated glass and create a glass enclosure that allows daylight into the building for the workers.

Why was Brin Glass best suited for the work?

Brin Contract Glazing was able to finish a large scope of work in a short period of time. The Brin team worked alongside the contractor and the design team in order to complete the project on time and give the client the end result that they wanted.

7201 Metro Blvd.

Contact

PCL Construction: Joe Kukulski

Project Start July 2020

Project End March 2021

Executed By Brin Contract
Glazing



Top: Installing panels for curtain wall

Bottom: Finished product